6. The supplier shall duly notify to the undersigned each and every consignment of cement received by him in his godown.

7. The supplier shall allow the undersigned or his authorised representative to inspect the stock in his godown at all reasonable times and shall permit the inspecting officer to collect cement for test from any barrel of the consignment. Such cement shall be tested by the Executive Engineer, Water Supply and Stores Division, in the P. W. Workshops.

8. If the cement so tested fails to satisfy the conditions of the British standard specification, the whole consignment will be rejected and the supplier shall remove same from that particular godown and shall guarantee to replace the same with fresh good stock within a week's time.

9. The rate offered by the supplier shall include cost of delivery of same in good condition at the stores of the Water Supply and Stores Division and shall be binding on the supplier for a period of 12 months from 25th January 1912.

10. The quantity of cement to be purchased from the supplier is not guaranteed.

K. SRINIVASA IYENGAR,
Executive Engineer.

BANGALORE CITY MUNICIPALITY.

Notice dated 16th January 1912.

Notice is hereby given that sealed tenders will be received by the President, City Municipality, Bangalore, for constructing a Vegetable Market at Akkipet in the Bangalore City, up to 2 P.M. on 3rd February 1912.

2. Plans and detailed estimate can be seen in the Municipal Executive Engineer's office during office hours.

3. The approximate quantities and items of works to be carried out are given below.

4. Each tenderer must definitely state the rate at which he would carry out each item. The work must be completed by the 31st of May 1912.

5. Tenders must be accompanied by a deposit of Rs. 200 (in cash or currency notes) as earnest money and be superscribed "Tender for constructing Akkipet Vegetable Market."

6. Final acceptance of any tender rests with the President, City Municipality, who does not bind himself to accept the lowest or any tender.

7. The name of the successful tenderer whose tender has been accepted will be posted on the notice board in the Municipal Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any attention.

8. The successful tenderer will be required to execute a bond within a week after the acceptance of his tender. In default, the tenderer will forfeit his earnest money and his contract will be considered *null and void.*

9. The earnest money of rejected tenderers will be returned to them on the above or any subsequent date by the President, City Municipality.

Items of work	*Per*	*Quantity*
Earthwork in excavation	C. yd.	144
Do filling	"	62
Concrete work	C. ft.	582
Stone pillars roughly dressed	S. ft.	1,132
Burnt stone slabs	"	1,924
Do roughly dressed	"	36
Teakwood work	C. ft.	120·88
Zinc sheet roofing	Sq.	26·64
Concrete filling and cement pointing	"	19·08
Gravelling the floor, etc., of stalls	Lump sum	
Tarring and whitewashing	Lump sum	
Iron pipe for connecting drains	R. ft.	24
Levelling the ground	Lump sum	
Burnt stone clay	C. ft.	698
Burnt brick in clay	"	489
Chunam plastering	Sq.	12·57
Chunam pointing	"	3·32
Brick in clay coping	R. ft.	180
Teakwood gates	S. ft.	90
Ornamental compound wall	R. ft.	62
Laterite	C. yd.	48
Gravel	"	16
Picking and forming	S. yd.	568
Consolidating laterite	C. yd.	48
Do gravel	"	16
Sanding (1	"	4

N. SUBBA RAO,
For *President.*